

SCHEDULE OF ITEMS						
Project:	Skidmore Day Use Improvements			Region:	Southwest Region 3	
Forest:	Prescott National Forest			District:	Verde Ranger District	
Base Bid Line Items						
Item Number	Schedule of Item Description	Method of Measure	Quantity	Pay Unit	Unit Price	Total Cost
151 (01)	Mobilization / Bonding	LSQ	1	LS	\$	\$
152 (01)	Construction Survey and Staking	LSQ	1	LS	\$	\$
154 (01)	Sampling and Testing, Concrete	LSQ	1	LS	\$	\$
157 (01)	SWPPP / Erosion Control Implementation	LSQ	1	LS	\$	\$
158 (01)	Watering for Dust Control	LSQ	1	LS	\$	\$
201 (01)	Clearing and Grubbing	EQ	8000	SY	\$	\$
203 (01)	Demolition, Posts, Guardrail, Veg., Tree-Limbing	LSQ	1	LS	\$	\$
204 (01)	Excavation	EQ	923	CY	\$	\$
204 (02)	Embankment	EQ	867	CY	\$	\$
204 (03)	Earthwork Compaction, Road / Parking Areas	EQ	5807	SY	\$	\$
204 (04)	Earthwork Compaction, Day Use and Path Areas	EQ	883	SY	\$	\$
211 (01)	Roadway Obliteration	LSQ	1	LS	\$	\$
251 (01)	Riprap, 6"-8", 8" Depth	EQ	304	CY	\$	\$
251 (02)	Landscape Boulders, 24" - 36"	AQ	40	EA	\$	\$
301 (01)	Surface Course, M.A.G. Base, Lower Parking Area	EQ	198	CY	\$	\$
301 (02)	Surface Course, Crushed Concrete / Asphalt Blend, Upper Roads and Parking	EQ	422	CY	\$	\$
301 (03)	Surface Course, Crushed Concrete / Asphalt Blend, Upper Paths	EQ	11	CY	\$	\$
311 (01)	Surface Course, 1/2" DG w/ Stabilizer, Lower Paths	EQ	32	CY	\$	\$
311 (02)	Surface Course, 1/2" DG w/ Stabilizer, Day Use Pads	EQ	10	CY	\$	\$
501 (01)	Accessible Parking Stall, Concrete, 6"	EQ	651	SF	\$	\$
501 (02)	Accessible Parking Stall, Van Horn Roll, 18"	EQ	43	LF	\$	\$
501 (03)	Accessible Parking Stall, Pavement Markings	LSQ	1	LS	\$	\$
501 (04)	Accessible Paths, Concrete	EQ	180	SF	\$	\$
600 (01)	Grill, Pedestal, w/ Footing, Install Only	AQ	2	EA	\$	\$
600 (02)	Picnic Table, Install Only	AQ	2	EA	\$	\$
600 (03)	Parking Bumper, Rubber, 72"L X 6"W X 4"H	AQ	14	EA	\$	\$
600 (04)	Trash Can, Bear-Saver, Install Only, w/ Conc. Pad	AQ	1	EA	\$	\$
602 (01)	Culvert, Galv. Steel, 20', 18" Dia., w/ Bedding	AQ	1	EA	\$	\$
619 (01)	Barrier, 2-Rail, w/ Posts, Steel	EQ	891	LF	\$	\$
633 (01)	Traffic Signs and Posts, By Location	AQ	9	EA	\$	\$
BASE BID TOTAL						\$
Option Bid Line Items						
Item Number	CLIN Description	Method of Measure	Quantity	Pay Unit	Unit Price	Total Cost
154 (02)	Sampling and Testing, Earthwork & Aggregate Compaction	LSQ	1	LS	\$	\$
600 (05)	Install Ramada, w/ Footings	AQ	2	EA	\$	\$
600 (06)	Install Vault Toilet, Double, Clovermist	LSQ	1	LS	\$	\$
619 (02)	Barrier, 2-Rail, w/ Posts, Steel, East Boundary to Mesa Drive	EQ	765	LF	\$	\$
619 (03)	Barrier, 2-Rail, w/ Posts, Steel, West Boundary from Toilet to Mesa Drive	EQ	635	LF	\$	\$
OPTION BID TOTAL						\$