

## Bureau of Land Management PV Condition Assessment

### Uncompahgre Field Office

|                   |                                                                                        |
|-------------------|----------------------------------------------------------------------------------------|
| Submitted on:     | April 9, 2025                                                                          |
| Submitted to:     | Bureau of Land Management                                                              |
| Submitted by:     | Ameresco, Inc.<br>111 Speen Street, Ste. 410<br>Framingham, MA 01701                   |
| Point of Contact: | Greg Caplan<br>VP Federal Business Development<br>gcaplan@ameresco.com<br>202-650-6214 |

## Table of Contents

|                                                   |                                                                                                                                         |          |
|---------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------|----------|
| <b>1.0</b>                                        | <b>PV Condition Assessment – Uncompahgre Field Office.....</b>                                                                          | <b>1</b> |
| <b>1.1</b>                                        | <b>Uncompahgre Field Office .....</b>                                                                                                   | <b>1</b> |
| 1.1.a                                             | PV condition assessment survey .....                                                                                                    | 1        |
| 1.1.b                                             | Visual Observation of Panels, Exposed Electrical Wire /<br>Insulation / Conduit, Inverters, and Associated Electrical<br>Equipment..... | 4        |
| 1.1.c                                             | Visual Inspection of Mounting Structure .....                                                                                           | 6        |
| 1.1.d                                             | Review and Verify Proper Grounding.....                                                                                                 | 7        |
| 1.1.e                                             | Verify Wiring, Conductors, and Conduit .....                                                                                            | 8        |
| 1.1.f                                             | Verify Safety Markings and Signs .....                                                                                                  | 8        |
| 1.1.g                                             | Net Metering .....                                                                                                                      | 8        |
| 1.1.h                                             | NEC Code Violations .....                                                                                                               | 8        |
| 1.1.i                                             | Performance Testing.....                                                                                                                | 8        |
| 1.1.j                                             | System Comparison and Recommendations .....                                                                                             | 10       |
| 1.1.k                                             | Energy Management System .....                                                                                                          | 14       |
| <b>Appendix A: Drawings .....</b>                 |                                                                                                                                         |          |
| <b>Appendix B: PVsyst Simulation Report .....</b> |                                                                                                                                         |          |

## 1.0 PV Condition Assessment – Uncompahgre Field Office

Perform condition assessments of 26 photovoltaic (PV) systems located in eight western states and determine the appropriate methods for transmitting data from those systems into the contractor's Energy Management Information System. Referred to collectively as PV field work.

### 1.1 Uncompahgre Field Office

32 kW of photovoltaic generation, with 1 – 30 kW inverter, North Office Building energy meter, and renewable energy meter (all existing)

#### 1.1.a PV condition assessment survey

Provide the following for each of the 26 PV sites described in Subparagraph I. Provide system description including block system diagram, and photographic records. Document PV system components including the following:




Figure 1: Current PV Configuration at Uncompahgre

i. *Panels: Manufacture, model number, individual panel watts, number of strings, total number of panels, total system watts, expected degradation rate.*

a. Array 1

- i. Manufacturer: Solar World
- ii. M/N: SW 245
- iii. Individual panel watts: 245W
- iv. Number of strings: 11
- v. Total number of panels: 132
- vi. Total system watts: 32 kW DC

b. Expected degradation rate: 19%

ii. *Description of mounting and mounting system, i.e., roof mounted with ballast or rack system, or ground mounted with steel rack system.*

Ground Mounted w/steel racking for both arrays

iii. *Inverter: Include inverter manufacture, model number, the type of interface capabilities of the inverter and whether it is currently connected for remote reading or is capable of being connected for remote reading.*

- a. Manufacturer: PV Powered
- b. Model number: PVP30kw
  - i. CEC efficiency: 93%
- c. Serial number: unreadable
- d. Communication Interface: RS-485
- e. EchoLabs not communicating during our visit



**Figure 2:** Current communication

- iv. *AC and DC disconnect, fuses, and circuit breakers. Provide manufacture and disconnect, fuse, and circuit breaker sizes. Verify DC disconnect is DC-rated.*
  - a. Inverter AC Disconnects #1 & #2 (AC Combiner Panels)
    - i. Siemens 30A 600VAC - 3 Pole
    - ii. Fuses - LITTELFUSE FLSR-30-ID W/INDICATOR, 30 AMP, CLASS RK5, DUAL ELEMENT, FLSR\_ID SERIES, 75-600VAC, TIME DELAY, FUSE
  - b. Main AC Disconnect
    - i. Siemens 60A 600VAC - 3 Pole
    - ii. Fuses - LITTELFUSE FLSR-60-ID W/INDICATOR, 60 AMP, CLASS RK5, DUAL ELEMENT, FLSR\_ID SERIES, 75-600VAC, TIME DELAY, FUSE
  - c. Array #1 & #2 DC Disconnects
    - i. Square D 60A - 600VAC & 600VDC - 3 Pole - Non-Fused
    - ii. Disconnects are DC rated
- v. *Description of rapid shutdown system.*

N/A. None present on these systems.

## 1.1.b Visual Observation of Panels, Exposed Electrical Wire / Insulation / Conduit, Inverters, and Associated Electrical Equipment

*Visual observation of the conditions of individual panels, exposed electrical wire/insulation/conduit, inverters, and associated electrical equipment. Photos shall be taken during the survey and included in the site assessment report. Common examples include cracked, damaged, or discolored individual panels, shaded or dirty panels, water intrusion in panel, corrosion and encapsulate yellowing, deteriorated electrical components such as strings, combiner box, disconnects, fuses, cables, conduit, or other exposed equipment, and equipment identified as beyond or near its estimated useful life.*

- i. *Modules and Array wiring*
  - a. PV wire and MC4 connector insulation is fine.
  - b. Wire management is very good.
- ii. *Inverters*
  - a. Inverter is not operational, electrical tech. spent the day troubleshooting and all were in fatal fault.
- iii. *AC & DC Disconnects & Fuses*
  - a. No corrosion or thermal issues present.
  - b. DC disconnects need to be cleaned and wasp nests removed.
- iv. *Conduit & Gutters*
  - a. No corrosion or thermal issues present.
- v. *DC Combiners & Strings*
  - a. No corrosion or thermal issues present.



**Figure 3:** Wire management and mountings are all very good condition

### 1.1.c Visual Inspection of Mounting Structure

*Visually inspect mounting structure to ensure roof penetrations are properly sealed, supports are structurally sound, and ballast systems are properly aligned.*



**Figure 4:** Uncompahgre site, showing the non-functional inverter

Supports are structurally sound, and ballast system properly aligned.

### 1.1.d Review and Verify Proper Grounding

*Review and verify proper grounding of all metallic surfaces including metallic PV module frames.*



**Figure 5:** Typical grounding at Uncompahgre

System is properly grounded.

---

### 1.1.e Verify Wiring, Conductors, and Conduit

---

*Verify wiring, conductors, and conduit are secure.*

---

Wiring, conductors, and conduit were all secure during our two site visits.

---

### 1.1.f Verify Safety Markings and Signs

---

*Verify safety markings and signs are installed and are legible.*

---

Fail, site needs new safety markings in accordance with federal and state regulations.

---

### 1.1.g Net Metering

---

*Determine whether the PV system is connected to the grid and set up for net metering. Verify net metering is operational.*

---

Net meter is readable, but the inverter is not operational.

---

### 1.1.h NEC Code Violations

---

*Identify and document NEC code violations.*

---

Pass, no NEC code violations were present during either of the two site visits.

---

### 1.1.i Performance Testing

---

*Performance testing: Provide and report the following:*

---

**1. Date and time.**

06/25/2024, 8:00 am

**2. Name and contact information of person performing tests/inspection.**

Chris Carelli, any questions regarding the test should be directed to Tim Mullen, [tmullen@ameresco.com](mailto:tmullen@ameresco.com) 410-507-6603

**3. Time of day and weather conditions.**

8 am, full sun

**4. Solar irradiance level.**

230 w/m<sup>2</sup>

**5. Ambient temperature.**

75° F

**6. Array temperature.**

90°F

**7. Open-circuit voltage (Voc) and polarity of each string. (Verify all strings have the same number of modules).**

a. Polarity

a. All Strings - Pass

b. Same Module Count on Strings

a. Pass

c. Array #1

a. Combiner #1

i. 410v

ii. 409v

iii. 410v

iv. 410v

v. 409v

vi. 409v

b. Combiner #2

i. 410v

ii. 410v

iii. 392v

iv. 410v

v. 410v

**8. Short-circuit current (Isc) of each string.**

8.25 Amps

**9. Confirm inverter is operational.**

Inverter is not operational

**10. Confirm inverter shuts down if AC utility is disconnected**

Inverter not operational

- 11. Maximum power point current (Imp) for each string. Current measurements for each string should be within 0.1A range of each other assuming consistent weather conditions, and all strings having same tilt and azimuth angle.**
  - a. No readings for inverter 1 since this information can only be recorded when inverter is operating.
- 12. Check condition of combiner box fuses for inoperable strings.**

Pass, no blown fuses.
- 13. Confirm inverter's power reading using independent meters. Afterwards, inverter power readings may be used for subsequent reporting.**

Inverters not operational.
- 14. Expected standard test condition (STC) power.**

32.3 kWp
- 15. System power output under actual conditions.**

Inverters are not operational.
- 16. Calculate the balance-of-system efficiency.**

Inverters are not operational.
- 17. Compare actual performance to expected STC power.**

Inverters are not operational.
- 18. Total power generated (kWh).**

Inverters are not operational.
- 19. Determine system expected degradation rate based upon manufacturer's literature.**

Inverters are not operational.
- 20. Determine actual system degradation rate.**

Inverters are not operational.

## 1.1.j System Comparison and Recommendations

### *System Comparison and Recommendations:*

- 1. Determine if additional troubleshooting, including the number of hours required to perform troubleshooting, is necessary to determine why the renewable system is not operating optimally.**

Inverters are not operational; it is recommended that the inverter be removed and replaced as outlined below.


**2. Compare on-site data measurements to manufacturer data.**

Not applicable, inverters are not operational.

**3. Provide recommendations for maintenance, repairs, and improvements to optimize the performance the system based upon site investigation and data analysis. Include a detailed cost estimate of the work required to restore, repair, or upgrade the system based upon recommendations.**

Ameresco recommends that the inoperable inverter be removed and replaced with a Sunny Tri power Core 1 33-US Sunny Tri-power 33kW inverters. We would test all solar panels and any with a short circuit will be bypassed. With the new inverters Ameresco would also install a new NEMA 4 junction box. This fix will make the PV field operational again at which time we can take baseline field readings and provide that data to BLM to compare system performance going forward.

If Ameresco does the inverter upgrade, we will also provide the required safety signage for the site for an additional \$400.00.



**Figure 6: Proposed new inverter configuration.**

4. Provide a projection of the remaining life expectancy of functional components, as well as for the overall system.

a. Solar Panels

- i. Current panels are 9.5 years old
- ii. Most manufacturers offer **warranties of 25–30 years**, guaranteeing at least **80% of the original efficiency** by the end of the period.
- iii. Many panels continue operating beyond 30 years with reduced efficiency.

b. Inverters

- i. Needs replacing

c) Racking and Wiring:

- i. Typically, last **30+ years** with minimal maintenance.
- ii. Corrosion or weather damage may require minor repairs over time.

**Factors Affecting Lifespan:**

- **Quality of components:** Higher-quality materials and reputable brands last longer.
- **Environmental conditions:** Harsh weather (extreme heat, humidity, hail, snow) can degrade components faster.
- **Maintenance:** Regular inspections and cleaning improve longevity.
- **Installation quality:** Poor installation can lead to premature failure of electrical and structural components.

5. Include a detailed cost estimate of the work required to restore/repair/upgrade the renewable energy systems, so they are fully functional.

**Table 1: Cost of installing a new inverter**

| Task                      | Hours     | OT Hours                       | Qty                | Material Description       | Material Cost Each         | Material Cost Total |
|---------------------------|-----------|--------------------------------|--------------------|----------------------------|----------------------------|---------------------|
| Electrician #1            | 16        |                                | 1                  | Sunny Core 1 33kw          | \$7,500.00                 | \$7,500.00          |
| Electrician #2            | 16        |                                | 15                 | MC4                        | \$3.50                     | \$52.50             |
|                           | 0         | 0                              | 30                 | #4 THHN                    | \$2.67                     | \$80.10             |
|                           | 0         | 0                              | 4                  | #4 bugs                    | \$27.00                    | \$108.00            |
|                           | 0         | 0                              | 1                  | 8x8x8 NEMA 4x Junction box | \$123.00                   | \$123.00            |
|                           | 0         | 0                              | 6                  | 1" Liquid Tight            | \$3.25                     | \$19.50             |
|                           |           |                                | 2                  | 1" Liquid Tight Connector  | \$7.52                     | \$15.04             |
| <b>Total</b>              | <b>32</b> | <b>0</b>                       |                    |                            |                            |                     |
| DDC Tech Labor            | 0         | 0                              | 0                  |                            | \$0.00                     | \$0.00              |
| Subcontractor             | Scope     | Price                          | Equipment          | Rental Time(month/week)    | Cost per unit              | Total               |
|                           |           | \$0.00                         |                    | 0                          | \$0.00                     | \$0.00              |
|                           |           | \$0.00                         |                    | 0                          | \$0.00                     | \$0.00              |
|                           |           | \$0.00                         |                    | 0                          | \$0.00                     | \$0.00              |
|                           |           | \$0.00                         |                    | 0                          | \$0.00                     | \$0.00              |
| <b>Total Hours Str</b>    | <b>32</b> |                                |                    |                            |                            |                     |
| <b>Total Hours OT</b>     | <b>0</b>  | <b>ESTIMATED HOURS</b>         | <b>TOTAL COSTS</b> |                            | <b>Total Material Cost</b> | <b>\$7,898.14</b>   |
| Supervisor Labor          | \$120.00  |                                | \$0.00             |                            | Equipment Costs            | \$0.00              |
| Field Tech Labor          | \$80.00   | 32                             | \$2,560.00         |                            | Subcontractor Costs        | \$0.00              |
| Field Tech Overtime Labor |           | 0                              | \$0.00             |                            | Install Labor              | \$0.00              |
|                           |           |                                | \$0.00             |                            | Other Labor                | \$2,560.00          |
|                           |           |                                | \$0.00             |                            | Total Mileage              | \$0.00              |
|                           |           |                                | \$0.00             |                            | Other Expenses             | \$0.00              |
|                           |           |                                |                    |                            |                            |                     |
|                           |           | <b>Cost/ Mile</b>              |                    |                            | <b>Overhead</b>            | <b>\$1,568.72</b>   |
| Mileage                   | 0         | 1.25                           | \$0.00             |                            | Profit                     | \$1,202.69          |
| Air Fare and Expenses     | 0         |                                |                    |                            | Total Bid Price            | \$13,229.55         |
| Overhead Percentage       | 15%       | 15% OH and 10% profit Minimum. |                    |                            |                            |                     |
| Profit Percentage         | 10%       |                                |                    |                            |                            |                     |

6. Report on PV systems and recommendations on work to restore/repair/upgrade them must also evaluate the cost to completely replace the PV system and compare the repair cost to the replacement cost of a similarly sized PV system. The field investigation report may confirm that based on the age of the existing PV array, replacing it may be the most economical solution. If replacement is the conclusion providing a detailed estimate on the cost of the repair of the existing system is not necessary. However, a justification describing the significant deficiencies of the existing system is to be provided.

Estimated cost of a new 33 kW system is in the ballpark of \$140,000.00 to \$165,000.00

## 1.1.k Energy Management System


*Reporting to the energy management system.*

1. **Detail and describe how electrical generation from each PV system and functional operation information will be transmitted to the contractor's energy management system.**

The PV system at Uncompahgre Field Office will use a Leviton IDAS-A8810-4G-S data acquisition system (DAS) to connect to the existing inverters Modus TCP (Ethernet). Data is collected by the DAS and uploaded periodically to AssetPlanner using a Cradlepoint cellular modem (typically a Cradlepoint S700). The communication between the DAS and AssetPlanner is encrypted. The DAS and cellular modem will be mounted in a NEMA 4 enclosure.

2. **The following information is to be transmitted from each PV site to the contractor's energy management system. The information is to be processed by the energy management system to create PV production reports, allow for comparison of each PV site, and calculation of emissions reduced, and their greenhouse gas equivalents.**

The DAS will provide current electrical energy production reported by each inverter on site. Inverter level metering will include voltage, current and power factor for each phase, as well as any alarms or fault codes generated by the inverter. In addition to the alarms generated by the inverters, AssetPlanner's Analytics Planner module includes a rules engine that includes rules to trigger alerts based on lower than expected production or loss of communication. The rules engine also allows for user define rules using any of the data points monitored by the DAS.



**Figure 7:** Overview of PV Data Acquisition System and AssetPlanner Analytics Planner for PV Systems

AssetPlanner will create PV production reports and calculate emissions reductions and greenhouse gas equivalents based on metered PV electric energy generation. It also has the site and portfolio level dashboards to monitor the current production and status of the systems and can optionally create public dashboards.




Figure 8: Sample portfolio and site status dashboards from AssetPlanner Analytics Planner for PV Systems



4. Include a detailed cost estimate of the work required to enable reporting to the energy management system. The cost estimate shall include detailed material breakouts, and labor hours. Use of lump sum costing is not acceptable.

The estimated cost of hardware and installation labor is \$4,838.85 and the estimated annual fees for software subscription and cellular data services are \$934. Detailed cost estimates are shown in the following two tables.

**Table 2:** Estimated DAS Hardware and Installation Costs for PV System Monitoring

| Description                                           | Part Number                          | Qty     | Unit Cost  | Total Cost        |
|-------------------------------------------------------|--------------------------------------|---------|------------|-------------------|
| Data Acquisition System with cell model and enclosure | Leviton<br>IDAS-A8810-4G-S           | 1       | \$3,150.00 | \$3,150.00        |
| Shipping (estimated)                                  |                                      | 1       | \$150.00   | \$150.00          |
| Installation Labor (on-site)                          | Electrician                          | 8 hours | \$71.40    | \$571.20          |
| Configuration & Commissioning Labor                   | Building Control<br>Systems Engineer | 5 hours | \$191.53   | \$ 957.65         |
| <b>Total Hardware Installation Cost</b>               |                                      |         |            | <b>\$4,828.85</b> |


**Table 3:** Estimated Annual Fees for PV System Monitoring

| Description                                                                  | Part Number   | Qty | Unit Cost | Total Cost      |
|------------------------------------------------------------------------------|---------------|-----|-----------|-----------------|
| Annual Subscription Fee for AssetPlanner Analytics Planner Module for DER-PV | AP-AnP-DER-PV | 1   | \$350.00  | \$350.00        |
| Cellular Data Plan Annual Fee                                                | ASG-Cell-1GB  | 1   | \$400.00  | \$400.00        |
| <b>Total Annual Fees</b>                                                     |               |     |           | <b>\$750.00</b> |

## Appendix A: Drawings

Plot Date:   
 NOTICE: THE DESIGNS SHOWN AND DESCRIBED HERE INCLUDING ALL TECHNICAL DRAWINGS, GRAPHICS AND MODELS ARE PROPRIETARY AND CANNOT BE COPIED, DUPLICATED OR COMMERCIALY EXPLOITED, IN WHOLE OR IN PART, WITHOUT THE EXPRESS WRITTEN PERMISSION OF AMERESCO

PV ARRAY



KEYNOTES

- 1 (E) INVERTER TO BE REMOVED
- 2 (E) PV MODULES TO REMAIN.
- 3 (E) ELECTRICAL EQUIPMENT TO BE REMOVED OR ABANDONED IN PLACE. COORDINATE WITH OWNER.

**AMERESCO**  
Green • Clean • Sustainable  
2355 EAST CAMELBACK ROAD,  
SUITE 410  
PHOENIX, AZ, 85016  
480.499.9200  
www.ameresco.com

**PVAMPS**  
ELECTRICAL ENGINEER  
5716 FOLSOM BLVD, #309  
SACRAMENTO, CA, 95819  
(916 425-4056) | PVAMPS.COM  
LICENSE # AZ 62410

**UNCOMPAHGRE FIELD OFFICE**  
2505 S TOWNSEND AVE,  
MONTROSE, CO 81401  
38.45903, -107.86794

SEALS AND SIGNATURES

| REV | ISSUED FOR | DATE |
|-----|------------|------|
|     |            |      |
|     |            |      |
|     |            |      |
|     |            |      |
|     |            |      |
|     |            |      |

DRAWN BY: JP  
CHECKED BY: MS

DRAWING TITLE


**SINGLE LINE  
DIAGRAM**

PROJECT NO.

DRAWING NUMBER  
**E-600**

Plot Date:   
 NOTICE: THE DESIGNS SHOWN AND DESCRIBED HERE INCLUDING ALL TECHNICAL DRAWINGS, GRAPHICS AND MODELS ARE PROPRIETARY AND CANNOT BE COPIED, DUPLICATED OR COMMERCIALY EXPLOITED, IN WHOLE OR IN PART, WITHOUT THE EXPRESS WRITTEN PERMISSION OF AMERESCO

PV ARRAY



KEYNOTES

- 1 EXTEND EACH STRING WIRE TO INVERTER LOCATION. ATTACH AMPHENOL H4 PLUS CONNECTORS (VERIFY WITH SMA) AND DIRECTLY CONNECT THE STRING WIRE TO INVERTER TERMINALS. INVERTER MPPT RANGE 330V-800V.
- 2 TERMINATE INVERTER OUTPUT CIRCUIT CONDUCTORS AT 50A/3P BREAKER.



2355 EAST CAMELBACK ROAD,  
SUITE 410  
PHOENIX, AZ, 85016  
480.499.9200  
www.ameresco.com



**PVAMPS**  
ELECTRICAL ENGINEER  
5716 FOLSOM BLVD, #309  
SACRAMENTO, CA, 95819  
(916 425-4056) | PVAMPS.COM  
LICENSE # AZ 62410

UNCOMPAHGRE FIELD OFFICE

2505 S TOWNSEND AVE,  
MONTROSE, CO 81401  
38.45903, -107.86794

SEALS AND SIGNATURES

| REV | ISSUED FOR | DATE |
|-----|------------|------|
|     |            |      |
|     |            |      |
|     |            |      |
|     |            |      |
|     |            |      |
|     |            |      |

DRAWN BY: JP  
CHECKED BY: MS

DRAWING TITLE

**SINGLE LINE  
DIAGRAM**

PROJECT NO.

DRAWING NUMBER  
**E-600**

## Appendix B: PVsyst Simulation Report

# PVsyst - Simulation report

## Grid-Connected System

Project: Uncompahgre Montrose Field Office

Variant: Uncompahgre Montrose Field Office v01\_2025-03-21

Sheds, single array

System power: 32.3 kWp

Montrose Co. Arpt - United States



# Project: Uncompahgre Montrose Field Office

## Variant: Uncompahgre Montrose Field Office v01\_2025-03-21

PVsyst V8.0.6

VC0, Simulation date:

21/03/25 08:43

with V8.0.6

PV AMPS (United States)

### Project summary

|                   |                      |                  |
|-------------------|----------------------|------------------|
| Geographical Site | Situation            | Project settings |
| Montrose Co. Arpt | Latitude 38.50 °N    | Albedo 0.20      |
| United States     | Longitude -107.90 °W |                  |
|                   | Altitude 1744 m      |                  |
|                   | Time zone UTC-7      |                  |
| Weather data      |                      |                  |
| Montrose Co. Arpt |                      |                  |
| NREL NSRD : TMY3  |                      |                  |

### System summary

|                          |                                |                       |
|--------------------------|--------------------------------|-----------------------|
| Grid-Connected System    | Sheds, single array            |                       |
| Orientation #1           | Near Shadings                  | User's needs          |
| Fixed plane              | Linear shadings : Fast (table) | Unlimited load (grid) |
| Tilt/Azimuth 30 / 0 °    |                                |                       |
| System information       |                                |                       |
| PV Array                 | Inverters                      |                       |
| Nb. of modules 132 units | Nb. of units 1 unit            |                       |
| Pnom total 32.3 kWp      | Pnom total 30.0 kWac           |                       |
|                          | Pnom ratio 1.078               |                       |

### Results summary

|                                |                                       |                        |
|--------------------------------|---------------------------------------|------------------------|
| Produced Energy 48895 kWh/year | Specific production 1512 kWh/kWp/year | Perf. Ratio PR 77.62 % |
|--------------------------------|---------------------------------------|------------------------|

### Table of contents

|                                                             |   |
|-------------------------------------------------------------|---|
| Project and results summary                                 | 2 |
| General parameters, PV Array Characteristics, System losses | 3 |
| Near shading definition - Iso-shadings diagram              | 4 |
| Main results                                                | 5 |
| Loss diagram                                                | 6 |
| Predef. graphs                                              | 7 |
| Single-line diagram                                         | 8 |



Project: Uncompahgre Montrose Field Office  
Variant: Uncompahgre Montrose Field Office v01\_2025-03-21

PVsyst V8.0.6

VC0, Simulation date:  
21/03/25 08:43  
with V8.0.6

PV AMPS (United States)

General parameters

|                       |          |                                |         |
|-----------------------|----------|--------------------------------|---------|
| Grid-Connected System |          | Sheds, single array            |         |
| Orientation #1        |          | Sheds configuration            |         |
| Fixed plane           |          | Nb. of sheds                   | 3 units |
| Tilt/Azimuth          | 30 / 0 ° | Single array                   |         |
|                       |          | Shading limit angle            |         |
|                       |          | Limit profile angle            | 18.5 °  |
| Models used           |          | Horizon                        |         |
| Transposition         | Perez    | Free Horizon                   |         |
| Diffuse               | Imported |                                |         |
| Circumsolar           | separate |                                |         |
| User's needs          |          | Near Shadings                  |         |
| Unlimited load (grid) |          | Linear shadings : Fast (table) |         |
|                       |          | Sizes                          |         |
|                       |          | Sheds spacing                  | 8.00 m  |
|                       |          | Collector width                | 3.37 m  |
|                       |          | Average GCR                    | 42.1 %  |
|                       |          | Top inactive band              | 0.02 m  |
|                       |          | Bottom inactive band           | 0.02 m  |

PV Array Characteristics

|                            |                          |                            |              |
|----------------------------|--------------------------|----------------------------|--------------|
| PV module                  |                          | Inverter                   |              |
| Manufacturer               | SolarWorld               | Manufacturer               | PV Powered   |
| Model                      | SW 245 Mono              | Model                      | PVP 30KW-480 |
| (Original PVsyst database) |                          | (Original PVsyst database) |              |
| Unit Nom. Power            | 245 Wp                   | Unit Nom. Power            | 30.0 kWac    |
| Number of PV modules       | 132 units                | Number of inverters        | 1 unit       |
| Nominal (STC)              | 32.3 kWp                 | Total power                | 30.0 kWac    |
| Modules                    | 11 string x 12 In series | Operating voltage          | 295-500 V    |
| At operating cond. (50°C)  |                          | Pnom ratio (DC:AC)         | 1.08         |
| Pmpp                       | 28.80 kWp                |                            |              |
| U mpp                      | 333 V                    |                            |              |
| I mpp                      | 86 A                     |                            |              |
| Total PV power             |                          | Total inverter power       |              |
| Nominal (STC)              | 32 kWp                   | Total power                | 30 kWac      |
| Total                      | 132 modules              | Number of inverters        | 1 unit       |
| Module area                | 221 m²                   | Pnom ratio                 | 1.08         |

Array losses

|                                            |               |                       |  |                                         |  |
|--------------------------------------------|---------------|-----------------------|--|-----------------------------------------|--|
| Thermal Loss factor                        |               | DC wiring losses      |  | Module Quality Loss                     |  |
| Module temperature according to irradiance |               | Global array res.     |  | Loss Fraction                           |  |
| Uc (const)                                 | 20.0 W/m²K    | 65 mΩ                 |  | 1.5 %                                   |  |
| Uv (wind)                                  | 0.0 W/m²K/m/s | Loss Fraction         |  | 1.5 % at STC                            |  |
| Module mismatch losses                     |               | Strings Mismatch loss |  | IAM loss factor                         |  |
| Loss Fraction                              |               | Loss Fraction         |  | ASHRAE Param.: IAM = 1 - bo (1/cosi -1) |  |
| 2.0 % at MPP                               |               | 0.2 %                 |  | bo Param.                               |  |
|                                            |               |                       |  | 0.05                                    |  |

AC wiring losses

|                                        |                      |
|----------------------------------------|----------------------|
| Inv. output line up to injection point |                      |
| Inverter voltage                       | 480 Vac tri          |
| Loss Fraction                          | 1.00 % at STC        |
| Inverter: PVP 30KW-480                 |                      |
| Wire section (1 Inv.)                  | Copper 1 x 3 x 6 mm² |
| Wires length                           | 24 m                 |




Project: Uncompahgre Montrose Field Office  
Variant: Uncompahgre Montrose Field Office v01\_2025-03-21

PVsyst V8.0.6  
VC0, Simulation date:  
21/03/25 08:43  
with V8.0.6

PV AMPS (United States)

Near shadings parameter


Perspective of the PV-field and surrounding shading scene



Iso-shadings diagram

Orientation #1

Fixed plane, Tilts/azimuths: 30°/ 0°





Project: Uncompahgre Montrose Field Office  
Variant: Uncompahgre Montrose Field Office v01\_2025-03-21

PVsyst V8.0.6

VC0, Simulation date:  
21/03/25 08:43  
with V8.0.6

PV AMPS (United States)

Main results

System Production

Produced Energy 48895 kWh/year


Specific production

1512 kWh/kWp/year


Perf. Ratio PR

77.62 %

Normalized productions (per installed kWp)



Performance Ratio PR



Balances and main results

|           | GlobHor<br>kWh/m <sup>2</sup> | DiffHor<br>kWh/m <sup>2</sup> | T_Amb<br>°C | GlobInc<br>kWh/m <sup>2</sup> | GlobEff<br>kWh/m <sup>2</sup> | EArray<br>kWh | E_Grid<br>kWh | PR<br>ratio |
|-----------|-------------------------------|-------------------------------|-------------|-------------------------------|-------------------------------|---------------|---------------|-------------|
| January   | 71.5                          | 31.25                         | -3.60       | 113.2                         | 108.2                         | 3371          | 3135          | 0.856       |
| February  | 81.3                          | 40.71                         | 1.60        | 110.6                         | 106.3                         | 3225          | 2998          | 0.838       |
| March     | 127.5                         | 51.21                         | 3.83        | 155.8                         | 150.2                         | 4432          | 4122          | 0.818       |
| April     | 151.8                         | 59.55                         | 7.28        | 162.9                         | 156.4                         | 4468          | 4153          | 0.788       |
| May       | 192.2                         | 69.48                         | 15.71       | 187.2                         | 179.1                         | 4936          | 4592          | 0.758       |
| June      | 235.7                         | 55.85                         | 21.71       | 219.4                         | 210.5                         | 5493          | 5110          | 0.720       |
| July      | 182.9                         | 72.02                         | 22.05       | 174.2                         | 166.6                         | 4442          | 4129          | 0.733       |
| August    | 184.7                         | 60.99                         | 21.99       | 191.4                         | 183.8                         | 4860          | 4527          | 0.731       |
| September | 154.3                         | 46.87                         | 18.86       | 182.9                         | 176.2                         | 4723          | 4399          | 0.744       |
| October   | 123.0                         | 37.61                         | 10.60       | 169.2                         | 163.6                         | 4598          | 4280          | 0.782       |
| November  | 93.3                          | 21.95                         | 4.00        | 155.9                         | 149.8                         | 4355          | 4058          | 0.805       |
| December  | 70.1                          | 22.28                         | -2.44       | 124.9                         | 118.9                         | 3645          | 3391          | 0.839       |
| Year      | 1668.2                        | 569.77                        | 10.17       | 1947.7                        | 1869.6                        | 52547         | 48895         | 0.776       |

Legends

|         |                                              |        |                                             |
|---------|----------------------------------------------|--------|---------------------------------------------|
| GlobHor | Global horizontal irradiation                | EArray | Effective energy at the output of the array |
| DiffHor | Horizontal diffuse irradiation               | E_Grid | Energy injected into grid                   |
| T_Amb   | Ambient Temperature                          | PR     | Performance Ratio                           |
| GlobInc | Global incident in coll. plane               |        |                                             |
| GlobEff | Effective Global, corr. for IAM and shadings |        |                                             |




Project: Uncompahgre Montrose Field Office  
Variant: Uncompahgre Montrose Field Office v01\_2025-03-21

PVsyst V8.0.6  
VC0, Simulation date:  
21/03/25 08:43  
with V8.0.6

PV AMPS (United States)

Loss diagram



**Global horizontal irradiation**

**Global incident in coll. plane**

Near Shadings: irradiance loss

IAM factor on global

**Effective irradiation on collectors**

PV conversion

**Array nominal energy (at STC effic.)**

PV loss due to irradiance level

PV loss due to temperature

Module quality loss

Mismatch loss, modules and strings

Ohmic wiring loss

**Array virtual energy at MPP**

Inverter Loss during operation (efficiency)

Inverter Loss over nominal inv. power

Inverter Loss due to max. input current

Inverter Loss over nominal inv. voltage

Inverter Loss due to power threshold

Inverter Loss due to voltage threshold

**Available Energy at Inverter Output**

AC ohmic loss

**Energy injected into grid**




Project: Uncompahgre Montrose Field Office  
Variant: Uncompahgre Montrose Field Office v01\_2025-03-21

PVsyst V8.0.6  
VC0, Simulation date:  
21/03/25 08:43  
with V8.0.6


PV AMPS (United States)

Predef. graphs

Daily Input/Output diagram




System Output Power Distribution





PVsyst V8.0.6  
VC0, Simulation date:  
21/03/25 08:43  
with V8.0.6

# Single-line diagram



|           |                  |
|-----------|------------------|
| PV module | SW 245 Mono      |
| Inverter  | PVP 30KW-480     |
| String    | 12 x SW 245 Mono |

|                                                        |                         |
|--------------------------------------------------------|-------------------------|
| Uncompahgre Montrose Field Office                      | PV AMPS (United States) |
| VC0 : Uncompahgre Montrose Field Office v01_2025-03-21 | 21/03/25                |